Situated in The
 Month:
 Page:

 Township of Colebrook, County of
 August
 ONE

 Ashtabula, State of Ohio and known as
 being part of Original Lot 95 within said
 Year:
 of

 Township and township 8N, Range 3W
 Year:
 ONE
 ONE

 Survey for:
 David D. Detweiler and Esther A. Detweiler

Checked on October 29th, 2022 by RLK

### **BASIS OF RESEARCH AND RECORDS**

All county ownership research data and previous survey records were obtained from The County Recorder's Office and Map Room. All county centerline and right-of-way data was obtained from The County Engineer's Office.
 All state centerline and right-of-way data was obtained from The Ohio Department of Transportation Records.


# PPN 10-023-00-004-01 and 10-023-00-004-02 David D. Detweiler and Esther A. Detweiler 9090 Mains Road


DEEDS OF RECORD: Volume 776, Page 2232 and Volume 597, Page 1863

ZONING INFORMATION

#### Minimum Requirements

Minimum Frontage: 250' Mininum Acreage: 2.00 acres Minimum Setback: 100' Minimum Sideyard: 25' Minimum Rearyard: 40'






TRUE NORTH

ODOT VRS and CORS GNSS Network

O -Denotes 5/8" (diameter) x 30" (long) iron (steel) pin (#5 rebar) with yellow plastic cap bearing "KOSIE P.S. 8167" set c. -Denotes calculated measurement r. -Denotes record measurement d. -Denotes deed measurement p. -Denotes plat measurement u. -Denotes used measurement fd. -Denotes found monument PPN -Denotes permanent parcel number € /C.L. -Denotes centerline R/W -Denotes right-of-way (margin) L-Denotes lot line P-Denotes property line BCSU -Denotes monument found bent, coned, straightened and used BCO -Denotes monument found bent, coned and observed POB -Denotes point of beginning MP -Denotes "measured perpendicularly"

aka -Denotes "also known as" fka -Denotes "formerly known as" FB -Denotes "field book" TR -Denotes "Township Road" CH -Denotes "County Highway" ACRD -Denotes "Ashtabula County Records and Deeds" ACER -Denotes "Ashtabula County Engineer's Records" TCRD -Denotes "Trumbull County Records and Deeds" TCER -Denotes "Trumbull County Engineer's Records"

> 100 75 50 25 0 100 200 300 GRAPHIC SCALE: 1 <sup>inch</sup> equals 100 <sup>feet</sup>





## 29.560 COMBINED ACRE PARCEL

0.555 acres Right of Way (R/W)

Deed of Record: Permanent Parcel Number (PPN) 10-023-00-004-01, David D. Detweiler and Esther A. Detweiler, Volume 776, Page 2232 and PPN 10-023-00-004-02, David D. Detweiler and Esther A. Detweiler, Volume 597, Page 1863 of Ashtabula County Records and Deeds (ACRD). 9090 Mains Road.

Situated in the Township of Colebrook, County of Ashtabula, State of Ohio and known as being part of Original Lot 95 within said Township and Township 8N, Range 3W in the Connecticut Western Reserve and bounded and described as follows:

Commencing at a 3/4" iron pin found at the centerline intersection of Storey Road (Township Road 79, FB 398, 60 feet wide) and Mains Road (also known as Manes Road, Township Road 84, FB 378, 50 feet wide).

Thence South 01°14'09" East, along the centerline of said Mains Road, 3495.71 feet to the southwesterly corner of PPN 10-024-00-015-00 as conveyed to Edward Kassay and Carol Kassay, recorded in Volume 655, Page 1676 of ACRD.

Thence South 01°14'09" East, continuing along said centerline, 783.29 feet to the northwesterly corner of the parcel herein described and <u>The Principal Place of</u> <u>Beginning of this Survey</u>, located South 01°14'09" East, 4279.00 feet from said centerline intersection.

Thence North 89°48'03" East, along the northerly line of the parcel herein described, passing through a 5/8" iron pin set at 25.00 feet, a total distance of 1202.51 feet to a 5/8" iron pin set on a westerly line of PPN 10-024-00-014-03 as conveyed to Edward Kassay and Carol Kassay, recorded in Volume 754, Page 1494 of ACRD, being the northeasterly corner of the parcel herein described.

### 29.560 COMBINED ACRE PARCEL (continued)

Thence South 16°04'07" East, along said westerly line of Kassay's land, 68.78 feet to a 5/8" iron pin found at an angle point therein.

Thence South 15°58'58" East, along a westerly line of said Kassay's land and also along the westerly line of PPN 10-024-00-013-00 as conveyed to Sofie Zifko and Georgette M. Baliga-Zifko, Trustees, recorded in Volume 300, Page 461 of ACRD, passing through a 1/2" iron pin found at 926.80 feet, a total distance of 928.38 feet to the southwesterly corner thereof, on the northerly line of PPN 37-046555 as conveyed to Melvin D. Byler and Ida M. Byler, recorded in INST 201206110015064 of Trumbull County Records and Deeds (TCRD), being the southeasterly corner of the parcel herein described.

Thence South 89°41'15" West, along said northerly line of Byler's land, along the northerly line of PPN 37-046653 as conveyed to Mellisa A. Ciambrone and Kevin J. Ciambrone, recorded in INST 201309180022285 of TCRD, passing by a 5/8" iron pin with cap bearing "J.N. FRANCIS S6916 3991261" found 0.32' south of the property line at 732.14 feet, passing by a 5/8" iron pin found 0.21' north of the property line at 1476.00 feet and a 5/8" iron pin set at 1489.40 feet, a total distance of 1514.70 feet to the northwesterly corner thereof, on the centerline of the aforesaid Mains Road, being the southwesterly corner of the parcel herein described.

Thence North 08°36'54" East, along said centerline, a frontage distance (in part) of 340.58 feet to a 3/4" iron pin found at an angle point therein.

Thence North 01°14'09" West, continuing along said centerline, a frontage distance (in part) of 626.08 to <u>The Principal Place of Beginning of this Survey</u> and containing 29.560 acres of land, of which, 0.555 acres are within the R/W of said Mains Road, leaving 29.005 acres of land exclusive of said R/W, surveyed in October of 2022 by D.B. Kosie and Associates, LLC, Robert L. Kosie, Registered Professional Land Surveyor 8167. Bearings are to True North using The ODOT VRS and CORS GNSS network (NAD83 - 2011, NAVD88, GRS80, and Geoid18). Distances are based on US Survey Foot Conversion (feet with decimal parts). Be the same, more or less, but subject to all legal highways, conditions, assignments, agreements, easements, restrictions and encumbrances.

The intent of this survey is to combine 1.840 acres of land that was divided from PPN 10-023-00-004-01 as conveyed to David D. Detweiler and Esther A. Detweiler, Volume 776, Page 2232 of ACRD together with PPN 10-023-00-004-02 as

### 29.560 COMBINED ACRE PARCEL (continued)

conveyed to David D. Detweiler and Esther A. Detweiler, recorded in Volume 597, Page 1863 of ACRD. Known as being 9090 Mains Road.

All 5/8" iron pins set shown herein noted as being 5/8" x 30" iron (steel) rebar pins (#5 rebar) with yellow plastic cap bearing "KOSIE P.S. 8167".





Robert L. Kosie, Sr., Ohio Certified Registered Professional Surveyor 8167 Signed and sealed on October 29th, 2022