TRUE NORTH (Geodetic) ODOT VRS and CORS GNSS Network NAD83 (2011), NAVD88, GRS80, Geoid18



200 150 100 50 0 GRAPHIC SCALE: 1 inch equals 200 feet

-Denotes 5/8" (diameter) x 30" (long) iron (steel) pin (#5 rebar) with yellow plastic cap bearing "KOSIE P.S. 8167" set c. -Denotes calculated measurement r. -Denotes record measurement d. -Denotes deed measurement p. -Denotes plat measurement o. -Denotes observed measurement u. -Denotes used measurement m. -Denotes measured distance fd. -Denotes found monument PPN -Denotes permanent parcel number INST -Denotes instrument number DN -Denotes document number AFN -Denotes automatic file number Ç /C.L. -Denotes centerline R/W -Denotes right-of-way (margin) 4 -Denotes lot line ₽-Denotes property line BCSU -Denotes monument found bent, coned, straightened and used BCO -Denotes monument found bent, coned and observed POB -Denotes point of beginning MP -Denotes "measured perpendicularly" aka -Denotes "also known as" fka -Denotes "formerly known as" FB -Denotes "field book" TR -Denotes "Township Road" CH -Denotes "County Highway"

ACRD -Denotes "Ashtabula County Records and Deeds"

ACER -Denotes "Ashtabula County Engineer's Records"

PEZAR -Denotes "James A. Pezar" See References

SLAY -Denotes "Jerry Slay" See References

CSS -Denotes "Crabb's Surveying Service" See References

This map of survey prepared by D.B. Kosie & Associates, LLC
Professional Land Surveying 11040 Madison Road

Montville, Ohio 44064

www.dbksurveys.com

## **REFERENCES**

\*The undated survey prepared by James M. Peter, Registered Surveyor 6420, recorded in Volume 653, Page 1652 of ACRD. \*The 1934 Road Alignment Record of Pymatuning Lake road filed as 0274 (Sec.H-K) Pymatuning Lake.pdf of ACER. \*The July, 1961 surveyor of the Cyphert Allotment prepared by W.O. Weir, Registered Surveyor 2041, recorded in Volume 11, Page 66 of ACRD. \* The July 24, 2019 survey prepared by Jerry Slay, Ohio Professional Surveyor 5298, recorded in Volume 691, Page 1766 of ACRD. \*The December 27, 2012 survey prepared by Jerry Slay, Professional Surveyor 5298, recorded in Volume 532, Page 2317 of ACRD. \*The October 2021, survey prepared by Timothy E. Stocker, Professional Surveyor 7245, recorded in Volume 754, Page 2192 of ACRD \*The June, 2022 survey prepared by Crabb's Surveying Service, Inc., Timothy E. Stocker, Professional Surveyor 7245, recorded in Volume 776, Page 1614 of ACRD. \*The November, 2022 survey prepared by James A. Pezar,

Professional Surveyor 7772, recorded in Volume 811, Page 1087 of ACRD

## MAP OF SURVEY OF PPN 45-002-00-015-00 Paul M. Miller, Rachel E. Miller, Marvin M. Miller and Emma J. Miller 6680 US Route 6

5/8" iron pin fd.

south 4.14, east 8.86'

not used in survey

with cap bearing

"PEZAR PS 7772"

fd. and used

73.78' c.

(73.75' PEZAR d.)


5/8" iron pin


5/8" iron pin

with cap bearing "PEZAR PS 7772"

fd. and used

DEED OF RECORD:







Volume 754, Page 604, second parcel 1691 Pymatuning Lake Road

PPN 45-002-00-007-00

Patricia Yarcusko and Theresa Harris

Volume 754, Page 604, first parcel

PPN 45-002-00-006-00

Gerald J. Bertram

Volume 7, Page 6998

PPN 45-002-00-005-00

Doreen P. Didino

Volume 681, Page 973

1751 Pymatuning Lake Road

5/8" iron pin

with cap bearing

"CRABBS SURVĚY

PS 7245"

46.00'

SLAY

1670.18' total c.

1596.40' c.

(1596.61' SLAY d.)

PPN 45-002-00-004-00

Noah S. Yoder and

Elizabeth M. Yoder Volume 691, Page 1766 1745 Pymatuning Lake Road

S 89°07'13" W

fd. and used

5/8" iron pin with

damaged cap

fd. and used

Robert L. Kosie, P.S. Registered Professional

Land Surveyor 8167 Signed and sealed on this 9th day of March, 2024. For any conflict resulting from electronic certifications please refer to ORC Section 1306.06, Electronic record or signature satisfies legal requirements.





# D.B. Kosie & Associates, LLC Professional Land Surveying



(440) 286-2131

11040 Madison Road Montville, Ohio 44064 www.dbksurveys.com



### **111.125 ACRE PARCEL**

0.423 acres Right of Way (R/W)

Deed of Record: Permanent Parcel Number (PPN) 45-002-00-015-00, Paul M. Miller, Rachel E. Miller, Marvin M. Miller and Emma J. Miller, Volume 809, Page 26 of Ashtabula County Records and Deeds (ACRD). 6680 US Route 6.

Situated in the Township of Richmond, County of Ashtabula and State of Ohio and known as being part of Original Lot 3 within said Township and Township 10N, Range 1W in The Connecticut Western Reserve and bounded and described as follows:

Commencing at the centerline intersection of Pymatuning Lake Road (County Highway 274, Section K, 60 feet wide) and US Route 6 (60 feet wide), referenced by a 1" iron pin in a monument box found North 88°18'30" East, 1218.02 feet therefrom, a 3/4" iron pin in a monument box found South 88°18'30" West, 8851.63 feet therefrom and a PK nail found north 0.16 feet and west 0.01 feet therefrom.

Thence South 88°18'30" West, along the centerline of said US Route 6, 1715.04 feet to the northwesterly corner of PPN 45-002-00-016-00 as conveyed to Susanne Boyle, recorded in Volume 386, Page 1960 of ACRD, being a northeasterly corner of the parcel herein described and **The Principal Place of Beginning of this Survey**.

Thence South 01°01'30" East, along the westerly line of said Boyle's land, passing through a 5/8" iron pin set at 30.00 feet, a total distance of 200.00 feet to a 5/8" iron pin set at the southwesterly corner thereof.

Thence North 88°18'30" East, along the southerly line of said Boyle's land, 300.00 feet to a 5/8" iron pin set at the southeasterly corner thereof, on the westerly line of PPN 45-002-00-015-01 as conveyed to Susanne Boyle, recorded in Volume 386, Page 1958 of ACRD, being a northeasterly corner of the parcel herein described.

Thence South 01°01'30" East, along said westerly line of Boyle's land, 560.00 feet to

#### 111.125 ACRE PARCEL (continued)

a 5/8" iron pin set at the southwesterly corner thereof.

Thence North 88°18'30" East, along the southerly line of said Boyle's land, 760.00 feet to a 5/8" iron pin set at the southeasterly corner thereof, on the westerly line of PPN 45-002-00-014-01 as conveyed to David A. Sanford, recorded in Volume 653, Page 1652 of ACRD, being a northeasterly corner of the parcel herein described.

Thence South 01°01'30" East, along said westerly line of Sanford's land and along the westerly line of the following parcels of land: PPN 45-002-00-013-00 as conveyed to Jeremy L. Harper, recorded in Volume 577, Page 927, PPN 45-002-00-012-00 as conveyed to Jerry Lawrence Latuk, recorded in Volume 776, Page 1614, PPN 45-002-00-009-00 as conveyed to James T. Johnson and Cathy A. Johnson, recorded in Volume 532, Page 2317, PPN 45-002-00-008-00 as conveyed to James T. Johnson and Cathy A. Johnson, recorded in Volume 754, Page 2192, PPN 45-002-10-005-00 as conveyed to John W. Houck and Debra Houck, recorded in Volume 238, Page 505 (being Sublot 1 in Cyphert Allotment, recorded in plat Volume 11, Page 66), crossing over the westerly side of Hickory Lake, along the westerly line of PPN 45-002-10-001-00 as conveyed to Patricia Yarcusko and Theresa Harris, recorded in Volume 754, Page 604, second parcel, PPN 45-002-00-007-00 as conveyed to Patricia Yarcusko and Theresa Harris, recorded in Volume 754, Page 604, first parcel, PPN 45-002-00-006-00 as conveyed to Gerald J. Bertram, recorded in Volume 7, Page 6998 and PPN 45-002-00-005-00 as conveyed to Doreen P. Didino, recorded in Volume 681, Page 973 of ACRD, passing by a 5/8" iron pin found 0.27 feet west of the property line at 100.12 feet, passing through a 5/8" iron pin with cap bearing "CRABBS SURVEY PS 7245" found at 2424.30 feet, a total distance of 2528.01 feet to a 5/8" iron pin set at a northeasterly corner of PPN 45-002-00-004-00 as conveyed to Noah S. Yoder and Elizabeth M. Yoder, recorded in Volume 691, Page 1766 of ACRD, being the southeasterly corner of the parcel herein described.

Thence South 89°07'13" West, along a northerly line of said Yoder's land, along a northerly line of PPN 45-002-00-017-00 as conveyed to Philip H. Dietrich, Trustee, recorded in Volume 811, Page 1087 of ACRD, passing through a 5/8" iron pin with cap bearing "PEZAR PS 7772" found at 1596.40 feet, a total distance of 1670.18 feet to a 5/8" iron pin with cap bearing "PEZAR PS 7772" found at the southwesterly corner of the parcel herein described.

Thence North 01°05'36" West, along an easterly line of said Dietrich's land, passing through a 5/8" iron pin with cap bearing "PEZAR PS 7772" found at 3234.30 feet, a total distance of 3264.30 feet to a northeasterly corner thereof, on the centerline of

#### 111.125 ACRE PARCEL (continued)

the aforesaid US Route 6, being the northwesterly corner of the parcel herein described.

Thence North 88°18'30" East, along said centerline, a frontage distance of 614.19 feet to <a href="The Principal Place of Beginning of this Survey">The Principal Place of Beginning of this Survey</a> and containing 111.125 acres of land, of which 0.423 acres are within the R/W of said US Route 6, leaving 110.702 acres of land exclusive of said R/W, surveyed in March of 2024 by D.B. Kosie and Associates, LLC, Robert L. Kosie, Registered Professional Land Surveyor 8167. Bearings are to True North using The ODOT VRS and CORS GNSS network (NAD83 - 2011, NAVD88, GRS80, and Geoid18). Distances are based on US Survey Foot Conversion (feet with decimal parts). Be the same, more or less, but subject to all legal highways, conditions, assignments, agreements, easements, restrictions and encumbrances.

The intent of this survey is to more accurately describe PPN 45-002-00-015-00 as conveyed to Paul M. Miller, Rachel E. Miller, Marvin M. Miller and Emma J. Miller, recorded in Volume 809, Page 26 of ACRD. Known as being 6680 US Route 6.

All 5/8" iron pins set shown herein noted as being 5/8" x 30" iron (steel) rebar pins (#5 rebar) with yellow plastic cap bearing "KOSIE P.S. 8167".

All PK nails set shown herein notes as being 1/4" x 2" long, thick-shanked "Parker-Kalon Company" style masonry nails.



Robert L. Kosie, Sr., Ohio Certified Registered Professional Surveyor 8167 Signed and Sealed on

March 12th, 2024

